



Department of Public Works The Town of Ludlow, Massachusetts

Scope of Work for Parkview Street & Mountainview Street Following procurement M.G.L.c. 30, S 39M

August 20, 2021

RE: Installation of catch basins and leaching chambers.

The Ludlow Department of Public Works is currently seeking quotes to install six catch basins and six leaching chambers on Parkview Street and Mountainview Street.

We request a comprehensive written proposal of the cost associated with the following:

- Install six catch basins and leach chambers at six different locations between the two streets. The catch basins will be installed at the edge of road with the leaching chamber installed directly behind. The catch basin and leach chamber will be connected by a piece of twelve-inch HDPE pipe. The department will supply all the structures, brick, cement, pipe, stone, gravel and filter fabric as required. All work shall be completed to Town standards. Construction within the Public Way and Trench Permits will be required but all fees will be waived. All police details for the work will be at the expense of the Town.
- OSHA Training required
- 50% Payment Bond required if contract is more than \$25,000.
- Prevailing wages apply
- OSD or Blanket Contract Option

Work will need to be completed no later than October 6, 2021

Please provide a written quote for this project **no later than September 15, 2021 at 4:00 PM**. Please submit the quote via email to kbatista@ludlow.ma.us. **You will receive a response back that your email was received.**

If you have any questions, or would like to visit the site, please contact Ken Batista via email at kbatista@ludlow.ma.us

Sincerely,

Kenneth Batista
Operations Supervisor